

数量総括表

No. 1

工 種	種 別	規 格・寸 法	単位	数 量	摘 要
土工	オープン掘削	地山土量	m3	60	62.5
	土留掘削	地山土量	m3	80	75.1
	埋戻(1m未満)	締固め土量	m3	50	51.0
	埋戻(1m以上)	締固め土量	m3	50	49.7
	路床土	良質土 締固め土量	m3	8	8.4
	購入土	ほぐし土量	m3	9	9.3
	残土運搬	地山土量	m3	30	25.9
	残土処分	ほぐし土量	m3	30	25.9
	基面整正		m2	40	42.6
舗装工	仮復旧				
	舗装版切断	t=5cm	m	11	10.9
	舗装版撤去	t=5cm	m2	8	8.4
	殻運搬	アスファルト	m3	0.4	0.4
	殻処分	アスファルト	t	0.9	0.9
	仮表層	②粗粒度As(20) t=3cm	m2	8	8.4
	上層路盤	M-40 t=14cm	m2	8	8.4
	下層路盤	ARC-40 t=12cm	m2	8	8.4
	本復旧				
	舗装版切断	t=5cm	m	11	10.8
	舗装版撤去	t=5cm	m2	3	3.2
	舗装版撤去	t=3cm	m2	8	8.4
	殻運搬	アスファルト	m3	0.4	0.4
	殻処分	アスファルト	t	0.9	0.9
	上層路盤撤去		m3	0.2	0.2
	残土運搬	地山土量	m3	0.2	0.2
	残土処分	ほぐし土量	m3	0.2	0.2

数量総括表

No. 2

工 種	種 別	規 格・寸 法	単位	数 量	摘 要
	表層	⑤密粒度As(新20FH) t=5cm	m2	12	11.6
	区画線復旧				
	区画線	W=15cm	m	5	5.2
	区画線(止まれ)	W=15cm換算	m	16	16.0
排水施設工	CSB600		m	18	17.6
	BFB-450		m	28	27.5
	BF450	発生材	枚	13	13
	BFB-300	発生材	m	4	4.0
	プレキャスト集水桝	1000x1000x2800 3分割品	基	1	1
	集水桝	800x1200x1000	基	1	1
	集水桝再設置	500x500x800	基	1	1
	既設暗渠内モルタル充填		m3	3	2.7
撤去工	BFB-450撤去	172kg/m	m	39	38.8
	BFB-300撤去	96kg/m	m	4	4.0
	BF450撤去	105kg/枚	枚	24	24
	HP φ 500撤去	459kg/2.43m	m	3	3.2
	BFB-450取壊し		m3	2	1.66
	BF450取壊し		m3	0.5	0.46
	HP φ 500取壊し		m3	0.2	0.24
	殻運搬	鉄筋コンクリート	m3	2	2.36
	殻処分	鉄筋コンクリート	t	6	5.90
	集水桝撤去	500x500x800	基	1	1
	集水桝撤去取壊し	600x600x850	基	1	1
	殻運搬	無筋コンクリート	m3	1	0.61
	殻処分	無筋コンクリート	t	1	1.43

数量総括表

No. 3

[illegible]

下倉1号線

測 点	単 距	オープン掘削			土留掘削			埋戻(1m未満)			埋戻(1m以上)			備 考
		m ²	m ²	m ³	m ²	m ²	m ³	m ²	m ²	m ³	m ²	m ²	m ³	
NO.0	0.00	1.8						1.4			0.5			
0+4.60	4.60	4.9	3.35	15.4		0.00	0.0	1.4	1.40	6.4	2.7	1.60	7.4	
0+4.60'	0.00		2.45	0.0	2.7	1.35	0.0	0.7	1.05	0.0	1.2	1.95	0.0	
0+7.40	2.80		0.00	0.0	4.9	3.80	10.6	0.7	0.70	2.0	3.3	2.25	6.3	
0+10.60	3.20		0.00	0.0	4.9	4.90	15.7	0.7	0.70	2.2	1.4	2.35	7.5	
0+17.80	7.20		0.00	0.0	4.9	4.90	35.3	0.7	0.70	5.0	3.3	2.35	16.9	
NO.1	2.20	3.5	1.75	3.9		2.45	5.4	0.6	0.65	1.4	2.9	3.10	6.8	
1+2.04	2.04	0.9	2.20	4.5		0.00	0.0	0.6	0.60	1.2	1.8	2.35	4.8	
計	22.04			23.8			67.0			18.2			49.7	

下倉1号線

測 点	単 距	路床土												備 考
		m	m	m ²	m	m	m ²	m	m	m ²				
NO.0	0.00													
0+4.60	4.60		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0	
0+4.60'	0.00		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0	
0+7.40	2.80		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0	
0+10.60	3.20	1.6	0.80	2.6		0.00	0.0		0.00	0.0		0.00	0.0	
0+17.80	7.20		0.80	5.8		0.00	0.0		0.00	0.0		0.00	0.0	
NO.1	2.20		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0	
1+2.04	2.04		0.00	0.0		0.00	0.0		0.00	0.0		0.00	0.0	
計	22.04			8.4			0.0			0.0			0.0	

構造物土量計算書

構造物	延 長	オープン掘削		土留掘削		埋戻(1m未満)		埋戻(1m以上)		路床土				備 考
		m ²	m ³	m ²	m ³	m ²	m ³	m ²	m ³	m ²	m ³	m ²	m ³	
BFB450	38.8	0.9	34.9			0.6	23.3							L=14.7+12.8+11.3=38.8
集水桝 800x1200x1000	3.2	1.2	3.8			1.2	3.8							
プレキャスト集水桝 1000x1000x2800	3.0			2.7	8.1	1.9	5.7							
計			38.7		8.1		32.8							

数量集計表

工種及び名称: 舗装工

延長及び個数: 1式

名 称	規 格	単位	数 量	摘 要
仮復旧				
舗装版切断	t=5cm	m	10.9	
舗装版撤去	t=5cm	m ²	8.4	
殻運搬	アスファルト	m ³	0.4	8.4*0.05
殻処分	アスファルト	t	0.9	0.4*2.35t/m ³ =0.9
仮表層	②粗粒度As(20) t=3cm	m ²	8.4	
上層路盤	M-40 t=14cm	m ²	8.4	
下層路盤	ARC-40 t=12cm	m ²	8.4	
本復旧				
舗装版切断	t=5cm	m	10.8	
舗装版撤去	t=5cm	m ²	3.2	11.6-8.4=3.2
舗装版撤去	t=3cm	m ²	8.4	
殻運搬	アスファルト	m ³	0.4	3.2*0.05+8.4*0.03=0.4
殻処分	アスファルト	t	0.9	0.4*2.35t/m ³ =0.9
上層路盤撤去		m ³	0.2	8.4*0.02=0.2
残土運搬	地山土量	m ³	0.2	
残土処分	ほぐし土量	m ³	0.2	0.2*1.2=0.2
表層	⑤密粒度As(新20FH) t=5cm	m ²	11.6	
区画線復旧				
区画線	W=15cm	m	5.2	2.5+2.7=5.2
区画線(止まれ)	W=15cm換算	m	16.0	

構造物総数量計算書

構造物名称 CSB600

延長及び個数 L= 17.6 m

細目	形状寸法	10m当数量	単位	総数量	摘要
基礎材	RC-40 t=15cm	9.90	m2	17.42	
遠心ボックスカルバート	CSB600	4.17	本	7.34	
基面整正	別途集計	9.9	m2	17.4	
				0	
				0	
				0	
				0	
				0	
				0	
				0	
測点			位置	数量	摘要
NO.0 + 0.68 ~ NO.0 + 18.30				17.6	
計				17.6	

構造物総数量計算書

構造物名称 BFB-450

延長及び個数 L= 27.5 m

細目	形状寸法	10m当数量	単位	総数量	摘要
基礎材	RC-40 t=10cm	6.50	m2	17.88	
敷モルタル	1:3	0.14	m3	0.39	
BFB-450		5	本	13.75	
基面整正	別途集計	6.5	m2	17.9	
				0	
				0	
				0	
				0	
				0	
				0	
測点			位置	数量	摘要
NO.0 - 15.19 ~ NO.0				14.7	
NO.1 ~ NO.1 + 12.54				12.8	
計				27.5	

構造物延長計算書

構造物名称 BF450(発生材)

延長及び個数 N= 13 枚

測 点	位置	延長及び個数	摘 要
NO.1 ～ NO.1 + 12.54		13	
計		13	

構造物総数量計算書

構造物名称 BFB-300

延長及び個数 L= 4.0 m

細目	形状寸法	10m当数量	単位	総数量	摘要
基礎材	RC-40 t=10cm	5.00	m2	2.00	
敷モルタル	1:3	0.09	m3	0.04	
BFB-300	発生材	5	本	2	
基面整正	別途集計	5.0	m2	2.0	
				0	
				0	
				0	
				0	
				0	
				0	
測点			位置	数量	摘要
				4.0	
計				4.0	

数量集計表

工種及び名称: 撤去工

延長及び個数: 1式

[illegible]

