

			【六地区別】工事費算出表									
工種	種別 (施工区分No.)	単位	施工 No. MH No. 施工区分	別途計上 (端数処理)	1 10	2 10	3 10	4 10	5 10	6 10		
1. 蓋設置・撤去工			(計)									
蓋設置		組	6.00		1.00	1.00	1.00	1.00	1.00	1.00		
調整金具	H25	組	6.00		1.00	1.00	1.00	1.00	1.00	1.00		
調整金具	H45	組	0.00									
調整リング	H 50 (0.03t)	個	6.00		1.00	1.00	1.00	1.00	1.00	1.00		
調整リング	H100 (0.06t)	個	0.00									
調整リング	H150 (0.09t)	個	0.00									
無収縮モルタル	25kg 高流動性超早強	袋	6.00		1.00	1.00	1.00	1.00	1.00	1.00		
蓋撤去	受枠・調整リング共 400kg以下	組	6.00		1.00	1.00	1.00	1.00	1.00	1.00		
蓋処分	受枠共 0.09t	組	6.00		1.00	1.00	1.00	1.00	1.00	1.00		
2. 防護コンクリート取壊工												
構造物取壊	無筋Co	m ³	0.42		0.07	0.07	0.07	0.07	0.07	0.07		
殻運搬	無筋Co廃材	m ³	0.42		0.07	0.07	0.07	0.07	0.07	0.07		
廃材処理	無筋Co廃材	t	0.96		0.16	0.16	0.16	0.16	0.16	0.16		
廃リング運搬		個	6.00		1.00	1.00	1.00	1.00	1.00	1.00		
廃リング処分	二次製品廃材	t	0.18		0.03	0.03	0.03	0.03	0.03	0.03		
3. 舗装版取壊・仮復旧工												
舗装版切断	AS 15cm以下	m	40.80		6.80	6.80	6.80	6.80	6.80	6.80		
舗装版切断	AS 30cm以下	m	0.00									
舗装版破碎	AS 5cm(10cm以下)	m ²	11.64		1.94	1.94	1.94	1.94	1.94	1.94		
舗装版破碎	AS 10cm(10cm以下)	m ²	0.00									
舗装版破碎	AS cm(15cm以下)	m ²	0.00									
殻運搬	AS廃材	m ³	0.60		0.10	0.10	0.10	0.10	0.10	0.10		
廃材処理	AS廃材	t	1.44		0.24	0.24	0.24	0.24	0.24	0.24		
床掘り		m ³	1.74		0.29	0.29	0.29	0.29	0.29	0.29		
土砂等運搬		m ³	1.74		0.29	0.29	0.29	0.29	0.29	0.29		
下層・路盤工	ARC40 15cm(平均)1層	m ²	0.00									
上層路盤工	M40 10cm(平均)1層	m ²	0.00									
上層路盤工	M40 15cm(平均)1層	m ²	15.06		2.51	2.51	2.51	2.51	2.51	2.51		
仮表層工	⑧密粒度AS(13) 5cm	m ²	0.00									
4. 舗装復旧工												
舗装版切断	AS 15cm以下	m	0.00									
舗装版切断	AS 30cm以下	m	0.00									
舗装版破碎	AS 5cm(10cm以下)	m ²	0.00									
舗装版破碎	AS 10cm(10cm以下)	m ²	0.00									
舗装版破碎	AS cm(15cm以下)	m ²	0.00									
殻運搬	AS廃材(舗装復旧)	m ³	0.00									
廃材処理	AS廃材(舗装復旧)	t	0.00									
床掘り		m ³	0.00									
土砂等運搬		m ³	0.00									
不陸整正		m ²	0.00									
表層工	⑨密粒度AS(13F) 5cm	m ²	0.00									
表層工 消パイ	⑫密粒度AS(13FH)改質Ⅰ型 5cm	m ²	15.06		2.51	2.51						