

| 工種 | 種別 (施工区分No.) | 単位 | 施工 No. MH No. 施工区分 | 別途計上 (端数処理) | 1 | 2 | 3 | 4 | 5 | 6 | | |
|----------------|----------------------|----|--------------------------|----------------|------|------|------|------|------|------|--|--|
| | | | | | 12 | 12 | 12 | 12 | 12 | 12 | | |
| 1. 蓋設置・撤去工 | | | (計) | | | | | | | | | |
| 蓋設置 | | 組 | 6.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | |
| 調整金具 | H25 | 組 | 6.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | |
| 調整金具 | H45 | 組 | 0.00 | | | | | | | | | |
| 調整リング | H 50 (0.03t) | 個 | 6.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | |
| 調整リング | H100 (0.06t) | 個 | 0.00 | | | | | | | | | |
| 調整リング | H150 (0.09t) | 個 | 0.00 | | | | | | | | | |
| 無収縮モルタル | 25kg 高流動性超早強 | 袋 | 6.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | |
| 蓋撤去 | 受枠・調整リング共 400kg以下 | 組 | 6.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | |
| 蓋処分 | 受枠共 0.09t | 組 | 6.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | |
| 2. 防護コンクリート取壊工 | | | | | | | | | | | | |
| 構造物取壊 | 無筋Co | m3 | 0.00 | | | | | | | | | |
| 般運搬 | 無筋Co廃材 | m3 | 0.00 | | | | | | | | | |
| 廃材処理 | 無筋Co廃材 | t | 0.00 | | | | | | | | | |
| 廃リング運搬 | | 個 | 6.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | |
| 廃リング処分 | 二次製品廃材 | t | 0.18 | | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | 0.03 | | |
| 3. 舗装版取壊・仮復旧工 | | | | | | | | | | | | |
| 舗装版切断 | AS 15cm以下 | m | 40.80 | | 6.80 | 6.80 | 6.80 | 6.80 | 6.80 | 6.80 | | |
| 舗装版切断 | AS 30cm以下 | m | 0.00 | | | | | | | | | |
| 舗装版破碎 | AS 5cm(10cm以下) | m2 | 15.06 | | 2.51 | 2.51 | 2.51 | 2.51 | 2.51 | 2.51 | | |
| 舗装版破碎 | AS 10cm(10cm以下) | m2 | 0.00 | | | | | | | | | |
| 舗装版破碎 | AS cm(15cm以下) | m2 | 0.00 | | | | | | | | | |
| 般運搬 | AS廃材 | m3 | 0.78 | | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | | |
| 廃材処理 | AS廃材 | t | 1.86 | | 0.31 | 0.31 | 0.31 | 0.31 | 0.31 | 0.31 | | |
| 床掘り | | m3 | 2.28 | | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | | |
| 土砂等運搬 | | m3 | 2.28 | | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | | |
| 下層・路盤工 | ARC40 15cm(平均)1層 | m2 | 0.00 | | | | | | | | | |
| 上層路盤工 | M40 10cm(平均)1層 | m2 | 0.00 | | | | | | | | | |
| 上層路盤工 | M40 15cm(平均)1層 | m2 | 15.06 | | 2.51 | 2.51 | 2.51 | 2.51 | 2.51 | 2.51 | | |
| 仮表層工 | ⑧密粒度AS(13) 5cm | m2 | 0.00 | | | | | | | | | |
| 4. 舗装復旧工 | | | | | | | | | | | | |
| 舗装版切断 | AS 15cm以下 | m | 0.00 | | | | | | | | | |
| 舗装版切断 | AS 30cm以下 | m | 0.00 | | | | | | | | | |
| 舗装版破碎 | AS 5cm(10cm以下) | m2 | 0.00 | | | | | | | | | |
| 舗装版破碎 | AS 10cm(10cm以下) | m2 | 0.00 | | | | | | | | | |
| 舗装版破碎 | AS cm(15cm以下) | m2 | 0.00 | | | | | | | | | |
| 般運搬 | AS廃材(舗装復旧) | m3 | 0.00 | | | | | | | | | |
| 廃材処理 | AS廃材(舗装復旧) | t | 0.00 | | | | | | | | | |
| 床掘り | | m3 | 0.00 | | | | | | | | | |
| 土砂等運搬 | | m3 | 0.00 | | | | | | | | | |
| 不陸整正 | | m2 | 0.00 | | | | | | | | | |
| 表層工 | ⑨密粒度AS(13F) 5cm | m2 | 0.00 | | | | | | | | | |
| 表層工 消ハイ | ⑫密粒度AS(13FH)改質Ⅰ型 5cm | m2 | 15.06 | | 2.51 | 2.51 | 2.51 | 2.51 | 2.51 | 2.51 | | |
| 基層工N5 | ②粗粒度AS(20) 5cm | m2 | 0.00 | | | | | | | | | |
| 表層工N5 | ⑨密粒度AS(13F) 5cm | m2 | 0.00 | | | | | | | | | |