

| 数 量 総 括 表 | | | | | | NO.1 |
|-----------|---------|--------|----------------|-------|---------------------|------|
| 工 種 | 種 別 | 規 格 | 単位 | 数 量 | 摘 要 | |
| 土 工 | | | | | | |
| 仮設道路 | | | | | | |
| | 掘削 | 粘性土 | m ³ | 186.0 | | |
| | 盛土 | 粘性土 | m ³ | 51.0 | | |
| | 切土法面仕上げ | | m ² | 130.0 | | |
| | 盛土法面仕上げ | | m ² | 47.0 | | |
| | 路盤工 | CR40mm | m ³ | 38.0 | 191.3×0.20= | |
| | 残土処理 | | m ³ | 130.0 | | |
| 排水計画(堤体部) | | | | | | |
| | 掘削 | | m ³ | 271.0 | | |
| | 盛土 | | m ³ | 0.3 | | |
| | 床掘 | | m ³ | 6.0 | | |
| | 埋戻し | | m ³ | 2.0 | | |
| | 切土法面仕上げ | | m ² | 85.0 | | |
| | 盛土法面仕上げ | | m ² | 0.5 | | |
| | 基面整形 | | m ² | 9.0 | | |
| | 植生工 | 切土法面 | m ² | 85.0 | | |
| | 残土処理 | 特装車運搬 | m ³ | 274.0 | | |
| 排水計画(堤内部) | | | | | | |
| | 掘削 | | m ³ | 233.0 | | |
| | 床掘 | | m ³ | 19.0 | | |
| | 埋戻し | | m ³ | 7.0 | | |
| | 切土法面仕上げ | | m ² | 149.0 | | |
| | 基面整形 | | m ² | 28.0 | | |
| | 残土処理 | 特装車運搬 | m ³ | 244.0 | | |
| 水路工 | | | | | | |
| BF-500 | L=2.0m | | m | 49.0 | うち堤体部20.0m、堤内部29.0m | |
| BF-250 | L=2.0m | | m | 18.0 | | |
| 分水柵Ⅱ型(下) | | | 個 | 2.0 | | |

[illegible]

土工集計表

内 訳

| 工 種 | 種別・細別 | 規 格 | 単位 | 全 量 | 摘 要 |
|------------------|--------------|---------------------------|----------------|-------|-----|
| 仮設道路 | | | | | |
| 掘削 | | | m ³ | 186.3 | |
| 盛土 | | | m ³ | 50.8 | |
| 切土法面仕上げ | | | m ² | 129.6 | |
| 盛土法面仕上げ | | | m ² | 46.5 | |
| 路盤工 | クラッシャーラン40mm | 191.3×0.2= | m ³ | 38.2 | |
| 残土処理 | | 186.3-50.8×1.11= | m ³ | 129.9 | |
| | | | | | |
| 排水計画(堤体部) | | | | | |
| 掘削 | | | m ³ | 270.7 | |
| 盛土 | | | m ³ | 0.3 | |
| 床掘 | | | m ³ | 5.9 | |
| 埋戻し | | | m ³ | 1.6 | |
| 切土法面仕上げ | | | m ² | 85.0 | |
| 盛土法面仕上げ | | | m ² | 0.5 | |
| 基面整形 | | | m ² | 9.4 | |
| 植生工 | | | m ² | 85.0 | |
| 残土処理 | | 270.7+5.9-(0.3+1.6)×1.11= | m ³ | 274.4 | |
| | | | | | |
| 排水計画(堤内部) | | | | | |
| 掘削 | | | m ³ | 232.9 | |
| 床掘 | | | m ³ | 19.4 | |
| 埋戻し | | | m ³ | 7.1 | |
| 切土法面仕上げ | | | m ² | 149.2 | |
| 基面整形 | | | m ² | 27.2 | |
| 残土処理 | | 232.9+19.4-7.1×1.11= | m ³ | 244.4 | |
| | | | | | |



土 工 総 括 表

| | 掘削 | 盛土 | 床掘 | 埋戻し | 切土法面仕上げ | 盛土法面仕上げ | 基面整正 | 計 |
|------------------|-------|------|------|-----|---------|---------|------|---|
| | | | | | | | | |
| 仮 設 道 路 | 186.3 | 41.5 | | | 129.6 | 46.5 | | |
| | | | | | | | | |
| 仮設道路(入空工の う) | | 9.3 | | | | | | |
| | | | | | | | | |
| 計 | 186.3 | 50.8 | | | 129.6 | 46.5 | | |
| | | | | | | | | |
| 排水計画(堤体部) | 270.7 | 0.3 | 5.9 | 1.6 | 85.0 | 0.5 | 9.4 | |
| | | | | | | | | |
| 計 | 270.7 | 0.3 | 5.9 | 1.6 | 85.0 | 0.5 | 9.4 | |
| 排水計画(堤内部) | 232.9 | | 17.2 | 6.3 | 149.2 | | 24.8 | |
| | | | | | | | | |
| | | | | | | | | |
| 分水柵Ⅱ型(下) | | | 2.2 | 0.8 | | | 2.4 | |
| | | | | | | | | |
| 計 | 232.9 | | 19.4 | 7.1 | 149.2 | | 27.2 | |
| | | | | | | | | |
| | | | | | | | | |
| 合計 | 689.9 | 51.1 | 25.3 | 8.7 | 363.8 | 47.0 | 36.6 | |


水路工

内 訳

| 工 種 | 種別・細別 | 規 格 | 単位 | 全 量 | 摘 要 |
|----------|-------|--------|----|------|----------|
| BF-500 | | L=2.0m | m | 49.0 | 土工は本線に計上 |
| BF-250 | | L=2.0m | m | 18.0 | |
| 分水柵Ⅱ型(下) | | | 個 | 2.0 | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |



CA=0.2
RA=0.1



CA=0.8
RA=0.3

| | | | | | |
|--|---|--|---|------|--|
| | 計 | | m | 67.0 | |
| | | | | | |

| | | |
|---|---|---------------|
| 第 | 号 | |
| | | <u>BF-500</u> |
| 内 | 訳 | 10.0m当たり |

BF-500

内 訳

10.0m当たり

[illegible]

第 号

BF-250

内 訳

10.0m当たり


| 工 種 | 種別・細別 | 規 格 | 単位 | 全 量 | 摘 要 |
|----------|-------------|--|----------------|------|------------|
| ベンチフリューム | 250型 | 2.00 | 本 | 5.0 | 106Kg/2.0m |
| | | | | | |
| 基礎碎石 | クラッシャーランΦ40 | 10.0 0.35 0.10 | m ³ | 0.35 | |
| | | | | | |
| 計 | 掘削 | 10.0 0.2 | m ³ | 2.0 | |
| | | | | | |
| | 埋戻し | 10.0 0.1 | m ³ | 1.0 | |
| | |  <p>CA=0.2 RA=0.1</p> | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | 掘削 | 18.0 0.2 | m ³ | 3.6 | |
| | 埋戻し | 18.0 0.1 | m ³ | 1.8 | |
| | 基面整形 | 18.0 0.35 | m ² | 6.3 | |
| | | | | | |
| 計 | 計 | | m | 10.0 | |
| | | | | | |

| 第 号 | 内 訳 | 1個当たり |
|-----|-----------------|-------|
| | <u>分水柵Ⅱ型(下)</u> | |

分水枋Ⅱ型(下)

内 訳

1個当たり

| 工 種 | 種別・細別 | 規 格 | 単位 | 全 量 | 摘 要 |
|----------|-------------|---|----------------|------|------------|
| ベンチフリューム | 分水柵Ⅱ型 | (下) | 個 | 1.0 | 516Kg/1.0個 |
| | | | | | |
| 基礎碎石 | クラッシャーランΦ40 | 1.11 1.11 0.10 | m ³ | 0.12 | |
| | | | | | |
| 計 | 掘削 | 1.11 1.71 0.8 | m ³ | 1.1 | |
| | | | | | |
| | 埋戻し | 1.11 1.71 0.3 | m ³ | 0.4 | |
| | | | | | |
| | 基面整形 | 1.11 1.11 | m ² | 1.2 | |
| | |  <p>CA=0.8 RA=0.3</p> | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| 計 | 計 | | 個 | 1.0 | |
| | | | | | |

土 留 工

内 訳

[illegible]

仮設道路



| 測点 | 距 離 | | 掘削 | | 盛土 | | 切土法面仕上げ | | 盛土法面仕上げ | | 路盤工 | | | | | | | |
|--------|-----------|-------|-----|-------------------------|-----|------------------------|---------|-------------------------|---------|------------------------|-----|-------------------------|-----|-----------------------|-----|-----------------------|-----|-----------------------|
| | 点 間 | 平 均 | 断 面 | 立 積 | 断 面 | 立 積 | 法 長 | 面 積 | 法 長 | 面 積 | 幅員 | 面積 | 断 面 | 立 積 | 法 長 | 面 積 | 法 長 | 面 積 |
| NO.2 | 0.00 | 5.00 | 0.2 | 1.0 | 0.7 | 3.5 | 0.0 | 0.0 | 0.2 | 1.0 | 3.0 | 15.0 | | | | | | |
| 2+10.0 | 10.00 | 9.86 | 4.7 | 46.3 | 1.4 | 13.8 | 3.4 | 33.5 | 1.7 | 16.8 | 3.0 | 29.6 | | | | | | |
| IP.1 | 9.72 | 5.00 | 2.4 | 12.0 | 0.2 | 1.0 | 1.7 | 8.5 | 0.5 | 2.5 | 4.7 | 23.5 | | | | | | |
| NO.3 | 0.28 | 5.14 | 2.7 | 13.9 | 0.0 | 0.0 | 1.1 | 5.7 | 0.0 | 0.0 | 4.7 | 24.2 | | | | | | |
| 3+10.0 | 10.00 | 10.00 | 4.4 | 44.0 | 0.1 | 1.0 | 3.4 | 34.0 | 1.3 | 13.0 | 3.0 | 30.0 | | | | | | |
| NO.4 | 10.00 | 6.08 | 5.9 | 35.8 | 0.1 | 0.6 | 4.4 | 26.7 | 1.1 | 6.7 | 3.0 | 18.2 | | | | | | |
| IP.2 | 2.15 | 4.50 | 7.0 | 31.5 | 0.1 | 0.5 | 4.4 | 19.8 | 1.3 | 5.9 | 3.0 | 13.5 | | | | | | |
| 4+9.0 | 6.85 | 6.43 | 0.0 | 0.0 | 3.2 | 20.6 | 0.0 | 0.0 | 0.0 | 0.0 | 3.0 | 19.3 | | | | | | |
| 4+15.0 | 6.00 | 4.50 | 0.4 | 1.8 | 0.0 | 0.0 | 0.3 | 1.4 | 0.0 | 0.0 | 3.0 | 13.5 | | | | | | |
| 4+18.0 | 3.00 | 1.50 | 0.0 | 0.0 | 0.3 | 0.5 | 0.0 | 0.0 | 0.4 | 0.6 | 3.0 | 4.5 | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 計 | m 58.0 | 58.0 | | m ³ 186.3 | | m ³ 41.5 | | m ² 129.6 | | m ² 46.5 | | m ² 191.3 | | m ² 0.0 | | m ² 0.0 | | m ² 0.0 |

排水計画(堤体部)

| 測点 | 距 離 | | 掘削 | | 盛土 | | 床掘 | | 埋戻し | | 切土法面仕上げ | | 盛土法面仕上げ | | 基面整形 | | | |
|--------|------------|-------|------|-------------------------|-----|-----------------------|-----|-----------------------|-----|-----------------------|---------|------------------------|---------|-----------------------|------|-----------------------|-----|-----------------------|
| | 点 間 | 平 均 | 断 面 | 立 積 | 断 面 | 立 積 | 断 面 | 立 積 | 断 面 | 立 積 | 法 長 | 面 積 | 法 長 | 面 積 | 法 長 | 面 積 | 法 長 | 面 積 |
| 4+15.0 | 0.00 | 1.50 | 0.0 | 0.0 | 0.2 | 0.3 | 0.2 | 0.3 | 0.1 | 0.2 | 0.0 | 0.0 | 0.3 | 0.5 | 0.6 | 0.9 | | |
| 4+18.0 | 3.00 | 2.50 | 0.2 | 0.5 | 0.0 | 0.0 | 0.4 | 1.0 | 0.1 | 0.3 | 0.3 | 0.8 | 0.0 | 0.0 | 0.6 | 1.5 | | |
| NO.5 | 2.00 | 3.00 | 10.2 | 30.6 | 0.0 | 0.0 | 0.4 | 1.2 | 0.1 | 0.3 | 2.5 | 7.5 | 0.0 | 0.0 | 0.6 | 1.8 | | |
| 5+4.0 | 4.00 | 3.00 | 37.6 | 112.8 | 0.0 | 0.0 | 0.4 | 1.2 | 0.1 | 0.3 | 10.4 | 31.2 | 0.0 | 0.0 | 0.6 | 1.8 | | |
| 5+6.0 | 2.00 | 3.37 | 33.3 | 112.1 | 0.0 | 0.0 | 0.4 | 1.3 | 0.1 | 0.3 | 10.9 | 36.7 | 0.0 | 0.0 | 0.6 | 2.0 | | |
| IP.3 | 4.73 | 2.37 | 6.2 | 14.7 | 0.0 | 0.0 | 0.4 | 0.9 | 0.1 | 0.2 | 3.7 | 8.8 | 0.0 | 0.0 | 0.6 | 1.4 | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 計 | m 15.73 | 15.73 | | m ³ 270.7 | | m ³ 0.3 | | m ³ 5.9 | | m ³ 1.6 | | m ³ 85.0 | | m ² 0.5 | | m ² 9.4 | | m ² 0.0 |

排水計画(堤内部)

| 測点 | 距 離 | | 掘削 | | 盛土 | | 床掘 | | 埋戻し | | 切土法面仕上げ | | 盛土法面仕上げ | | 基面整形 | | | |
|-----------|------------|-------|-----|-------------------------|-----|-----------------------|-----|------------------------|-----|-----------------------|---------|-------------------------|---------|-----------------------|------|------------------------|-----|----------------|
| | 点 間 | 平 均 | 断 面 | 立 積 | 断 面 | 立 積 | 断 面 | 立 積 | 断 面 | 立 積 | 法 長 | 面 積 | 法 長 | 面 積 | 法 長 | 面 積 | 法 長 | 面 積 |
| IP.3 | 0.00 | 4.64 | 6.2 | 28.7 | 0.0 | 0.0 | 0.4 | 1.9 | 0.1 | 0.5 | 3.7 | 17.1 | 0.0 | 0.0 | 0.6 | 2.8 | | |
| NO.6 | 9.27 | 9.64 | 6.3 | 60.7 | 0.0 | 0.0 | 0.4 | 3.9 | 0.1 | 1.0 | 3.3 | 31.8 | 0.0 | 0.0 | 0.6 | 5.8 | | |
| 6+10.0 | 10.00 | 10.00 | 4.6 | 46.0 | 0.0 | 0.0 | 0.4 | 4.0 | 0.1 | 1.0 | 4.0 | 40.0 | 0.0 | 0.0 | 0.6 | 6.0 | | |
| NO.7 | 10.00 | 5.00 | 2.4 | 12.0 | 0.0 | 0.0 | 0.4 | 2.0 | 0.4 | 2.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.6 | 3.0 | | |
| | | | | | | | | | | | | | | | | | | |
| 計 | 29.27 | 29.27 | | 147.4 | | 0.0 | | 11.8 | | 4.5 | | 88.9 | | 0.0 | | 17.6 | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| IP.3 | 0.00 | 9.00 | 6.2 | 55.8 | 0.0 | 0.0 | 0.4 | 3.6 | 0.1 | 0.9 | 3.7 | 33.3 | 0.0 | 0.0 | 0.4 | 3.6 | | |
| P.3～IP3-1 | 18.00 | 9.00 | 3.3 | 29.7 | 0.0 | 0.0 | 0.2 | 1.8 | 0.1 | 0.9 | 3.0 | 27.0 | 0.0 | 0.0 | 0.4 | 3.6 | | |
| | | | | | | | | | | | | | | | | | | |
| 計 | 18.00 | 18.00 | | 85.5 | | 0.0 | | 5.4 | | 1.8 | | 60.3 | | 0.0 | | 7.2 | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| 計 | m 47.27 | 47.27 | | m ³ 232.9 | | m ³ 0.0 | | m ³ 17.2 | | m ³ 6.3 | | m ³ 149.2 | | m ² 0.0 | | m ² 24.8 | | m ² |

| | | | | | | | | | | | |
|--------|--------|--------|----------------|--|----------------|------|---|--|--|--|--|
| 第 号 | | 構造物撤去工 | | | | | | | | | |
| 内 訳 | | NO.1 | | | | | | | | | |
| 測 点 | 種別・細別 | 算 式 | | | 単位 | 全 量 | 摘 要 | | | | |
| BF-200 | 取壊し | m | m ² | | m ³ | 0.30 |  断面積=0.02m ² | | | | |
| | | 15.0 | 0.02 | | | | | | | | |
| | | | | | | | | | | | |
| BF-300 | 取壊し | m | m ² | | m ³ | 0.09 |  断面積=0.03m ² | | | | |
| | | 3.0 | 0.03 | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | m | Kg | | | | | | | | |
| | | | | | | | | | | | |
| 取壊し | 計 | | | | m ³ | 0.39 | | | | | |
| | BF-200 | 0.30 | 2.35 | | t | 0.71 | | | | | |
| | BF-300 | 0.09 | 2.35 | | t | 0.21 | | | | | |
| | 計 | | | | t | 0.92 | | | | | |
| | | | | | | | | | | | |
| | 計 | | | | 式 | 1.0 | | | | | |


第 号

仮 設 工

内 訳

仮設道路

| 工 種 | 種別・細別 | 算 式 | | | 単位 | 全 量 | 摘 要 |
|-------------------|--------|------------------------|------|----|----------------|------|------|
| | | 長さ | 巾 | 厚さ | | | |
| NO.4+9.0 敷鉄板 | W=1.5m | 6.0 | 1.50 | | m ² | 9.0 | 設置撤去 |
| | | | | | | | |
| NO.4+15.0 敷鉄板 | W=1.5m | 12.0 | 3.0 | | m ² | 36.0 | 設置撤去 |
| | | | | | | | |
| NO.4+9.0 大型土のう | | m ² 9.30 | 1.0 | | m ³ | 9.3 | 設置撤去 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |



| | | | | | | | |
|--|---|--|--|--|---|-----|--|
| | | | | | | | |
| | 計 | | | | 式 | 1.0 | |
| | | | | | | | |