

工種	種別 (施工区分No.)	単位	施工 No. MH No. 施工区分	別途計上 (端数処理)	1 12	2 12	3 12	4 12	5 12	6 12	7 12	8 12	9 12	10 12	11 12	12 12
1. 蓋設置・撤去工			(計)													
蓋設置		組	12.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
調整金具	H25	組	12.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
調整金具	H45	組	0.00													
調整リング	H 50 (0.03t)	個	12.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
調整リング	H100 (0.06t)	個	0.00													
調整リング	H150 (0.09t)	個	0.00													
無収縮モルタル	25kg 高流動性超早強	袋	12.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
蓋撤去	受枠・調整リング共 400kg以下	組	12.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
蓋処分	受枠共 0.09t	組	12.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
2. 防護コンクリート取壊工																
構造物取壊	無筋Co	m3	0.00													
般運搬	無筋Co廃材	m3	0.00													
廃材処理	無筋Co廃材	t	0.00													
廃リング運搬		個	12.00		1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
廃リング処分	二次製品廃材	t	0.36		0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.03
3. 舗装版取壊・仮復旧工																
舗装版切断	AS 15cm以下	m	81.60		6.80	6.80	6.80	6.80	6.80	6.80	6.80	6.80	6.80	6.80	6.80	6.80
舗装版切断	AS 30cm以下	m	0.00													
舗装版破碎	AS 5cm(10cm以下)	m2	30.12		2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51
舗装版破碎	AS 10cm(10cm以下)	m2	0.00													
舗装版破碎	AS cm(15cm以下)	m2	0.00													
般運搬	AS廃材	m3	1.56		0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13
廃材処理	AS廃材	t	3.72		0.31	0.31	0.31	0.31	0.31	0.31	0.31	0.31	0.31	0.31	0.31	0.31
床掘り		m3	4.56		0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38
土砂等運搬		m3	4.56		0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38	0.38
下層・路盤工	ARC40 15cm(平均)1層	m2	0.00													
上層路盤工	M40 10cm(平均)1層	m2	0.00													
上層路盤工	M40 15cm(平均)1層	m2	30.12		2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51	2.51
仮表層工	⑧密粒度AS(13) 5cm	m2	0.00													
4. 舗装復旧工																
舗装版切断	AS 15cm以下	m	0.00													
舗装版切断	AS 30cm以下	m	0.00													